Public Works (1937) Department

MS SERIES.

G.O. No. 1105

DATED 3-6-1937

[Despatch Abstract.]

POLICE DEPARTMENT.

Received 6 MAR 1937 19

ASSISTANT SECRETARY TO GOVT. HOME DEPARTMENT

SECRETARY TO GOVT. C 12 MAR 1937 PUBLIC WORKS DEPT.

Buildings - Electric installation - South Kanara District - Mangalore - Police Buildings - Provision of - Approval requested

Note U.O. 102/B-1 12-3

ENCLOSURES.
No.
Spare copies

Station Madras ; Dated the 5th March 1937.

From (Name) F. Sayers, Esquire,
Designation) Offg. Inspr.-Genl. of Police, Madras.

To The Secretary to the Government of Madras, Department.

Sir,

I have the honour to forward herewith for the approval of the Government the following estimates with plans for the provision of electric installation to the Police buildings at Mangalore in the South Kanara District where electric current is now available.

(1) Provision of electric installation to the District Police Office, Mangalore. Rs.880/-.

(2) Provision of electric installation to the Reserve School, Armoury and Reserve Inspector's Office Mangalore Rs.425/-.

(3) Provision of electric installation to the Hackney Carriage Office, Mangalore.

4) Provision of electric installation to the Mangalore Town Police Station. Rs.570/-.

5) Provision of electric installation to the Mangalore Taluk Police Station. Rs.220/-

2. Work in the District Police Office and other buildings has to be carried after dusk and the provision of electric lights is therefore. I consider necessary.

3. The proposal involves an additional expenditure of Rs.692/- per annum - vide comparative statement accompanying the estimates.

4. The work will be executed by the Public Works Department and the expenditure met from their grant for Police Minor Works in the Civil Works Estimate for 1937-1938.

I have the honour to be,

Sir

Your most obedient servant

for Inspr.-Genl. of Police.

P.M.N./3-3-37

POLICE DEPARTMENT.

Received ..... 19 *Registered*

Subject.

Buildings - Electric Installation South Kanara District - Mangalore - Police Buildings - Provision of - Approval requested.

ENCLOSURES.
No.
Spare copies

Station Madras, *Dated the* March 19 37.

From (Name) F. Sayers, Esquire

(Designation) Offg. Inspr.-Genl. of Police, Madras.

To The Secretary to the Government of Madras,

HOME Department.

Sir,

I have the honour to forward herewith for the approval of the Government the following estimates with plans for the provision of electric installation to the Police Buildings at Mangalore in the South Kanara District where electric current is now available.

(1) Provision of electric installation to the District Police Office, Mangalore. Rs.880/-.

(2) Provision of electric installation to the Reserve School, Armoury and Reserve Inspector's Office, Mangalore Rs.425/-.

(3) Provision of electric installation to the Hackney Carriage Office, Mangalore.

(4) Provision of electric installation to the Mangalore Town Police Station. Rs.570/-

(5) Provision of electric installation to the Mangalore Taluk Police Station. Rs.220/-

2. Work in the District Police Office and other buildings has to be carried after dusk and the provision of electric lights is therefore, I consider, necessary.

3. The proposal involves an additional expenditure of Rs.692/- per annum - vide comparative statement accompanying the estimates.

4. The work will be executed by the Public Works Department and the expenditure met from their grant for Police Minor Works in the Civil Works Estimate for 1937-1938.

I have the honour to be,

Sir,

Your most obedient servant,

for Inspr.-Genl. of Police.

P.M.N./3-3-37

443

ESTIMATE FORM—Abstract.

Est. No. 126/Mang/36-37 Plan E.E.Cl.No.122/Mang/36-37 (Revised)

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Amount. (5)	Total. (7)
			Rs.	Rs.	Rs.
1.	15Pts.	Wiring with 3/036 C.T.S.cable on teak wood fillets for lights.	11/-	Pt.	165/-
2.	5.Pts.	for fans.	12/-	"	60/-
3.	15.Nos.	Supplying and fixing single light pendants with assorted shade and 40 watt bulb.	3/-	Each	45/-
4.	5.Nos.	Supplying and fixing 230 volts A.C. ceiling fans with regulator down rod and fan clamps etc.,complete.	100/-	"	500/-
5.	1.No.	Supplying and fixing a 4 way distribution board with 10/15 amps.D.P. switch with fuses mounted suitably on teak wood board with swinging frame.	20/-	"	20/-
6.		Cost of service connection.		L.S.	69/-
7.		Contingencies.		L.S.	21/-
					380/-

The estimate provides for electric installation to the Office of the District Superintendent of Police, Mangalore. The provision in the estimate is the minimum requirements with reference to floor area etc.,

Electrical Engineer (General).

Countersigned
6/12/37
Dt Superintendent of Pol
S.Kanara.

Grand total of estimate ...

STATION

Date 193 .

Executive Engineer.

P.W.D. V-14- 65,736- 12-11 35 (6).

E. No. 32.

CIRCLE—

DIVISION— Electrical.

DISTRICT— South Canara.

TALUKS (OR ESTATE IN CASE OF ESTATE WORKS).
Mangalore.

ESTIMATE FORM—Abstract.

Financial head— 41.C.E.Provincial.

Budget head— Transferred.

Departmental head— Origianl Minor.

Main head— Police.

Sub-head—

Project of which
the work forms part—

Section—

Name of work—Electric Installation to the Office of the District Superintendant of Police, South Canara District. Mangalore.

Amount of estimate, Rs. 880/-

To be carried out by—Electricity Deptt.,

REFERENCES.

1. Ref:--R.C.No.2375/G1/34 dated 29-4-35 from the District Supdt. of Police,South Canara,Mangalore
2. Ref:--No.618/Genl/36 dated 28-2-36 from the Dist.Supdt.of Police,South Canara, Mangalore.
3. Ref:--R.C.No.1156/Genl/36 dated 17-10-36 from the Dist.Supdt.of Police, South Canara, Mangalore.
4. Ref:-R.C.2930/G1/36 dated 5-12-36 from the D.S.p.S.Canara, Mangalore

Est.No.130.Mangalore. 36-37

Encl:-Plan No.126.Mangalore. 36-37

ESTIMATE FORM—Abstract.

RECEIVED 22 DEC 1936 SOUTH KANARA

Item number. (1)	Quantity. (2)	Description of work.	Rate. (4)	Per (5)	Amount (6)	Total. (7)
			Rs.		Rs.	Rs.
2	Pts.	Wiring with 3/036 C.T.S. cable on teak wood fillets for lights.	11	Pt.	22	
2	Nos.	Supplying & fixing single light pendant with assorted shades & 40 Watt bulb.	3	E.	6	
1		Supplying & fixing a 5 amp. cut out board with 5 amp. D.P. tumblar switch etc., complete.	6	"	6	
		Cost of service connection.		L.S.	25	
		Contingencies.		"	1	
				Total,	Rs.	60/-

Report.

The estimate provics for Electric Installati to the Hackney carriage office, Mangalore. The provision in the estimate is the minimum requirements with reference to floor area etc.

Electrical Engineer (Genl).

Countersigned.

Mangalore, 26.8.36.

Executive Engineer.

Grand total of estimate ..

STATION

Date 198 .

Executive Engineer.

P.W.D. F.14- 15,000--20-9-35 (

E. [redacted] 32.

Circle—

Division— Electrical

District— South Canara

Taluks (or Estate in case of Estate Works).

Mangalore.

ESTIMATE FORM—Abstract.

Financial head— 41.C.W. Provincial.

Budget head— Transferred.

Departmental head— Original Minor.

Main head— Police.

Sub-head—

Project of which the work forms part—

Section—

Name of work— Electric Installation to Hackney carriage office, Mangalore.

Amount of estimate, Rs. 60/-

To be carried out by— Elec.Dept.

REFERENCES.

Ref.[illegible] R.C.No.2375/Genl/34,dated 29-4-35 and Ref.No.618/Genl/36, dated 28-2-36 from the Dist.Supdt. of Police, South Canara District, Mangalore.

ESTIMATE FORM—Abstract.

Est.No.128-R/MAN/36-37 Plan No.124/MAN/36-37

Item number. (1)	Quantity. (2)	Description of work (3)	Rate. (4)	Per (5)	Amount (6)	Total (7).
			Rs.		Rs.	Rs.
1.	18.Pts.	Wiring with 3/036 C.T.S.cable on teak wood fillete for lights.	11/-	Pt.	198/-	
2.	2.Pts.	" for fans.	12/-	"	24/-	
3.	15.Nos.	Supplying and fixing single light pendant with assorted shade and 40 watt bulbs.	3/-	Each	45	
4.	3.Nos.	" single light bracket fitting with green and white shade and 40 watt bulb.	5/-	"	~~45/-~~ 15	
5.	2.Nos.	Supplying and fixing 230 volts A.C.ceiling fans with regulator down rod fan clamps etc. complete.	100/-	"	200/-	
6.	1.No.	Supplying and fixing a 4 way distribution board with 10/15.amps.D.P. switch with fuses mounted on teak wood board with swinging frame.	20/-	"	20/-	
7.	10Yds.	Run of 7/036 C.T.S.cable on teak wood fillets for mains.	1-4-0	Yard	13/-	
8.		Cost of service connection.		L.S.	38/-	
9.		Contingencies.		L.S.	17/-	
						570/-

Report:--

The estimate provides for Electric installation to Town Police station Mangalore. The provision in the estimate is the minimum requirements with reference to floor

P.W.D. F.14—61,616—31-7-(

E. No. 32.

Circle—

Division—Electrical.

District—South Kanara.

Taluka (or Estate in case of Estate Works).

Mangalore.

ESTIMATE FORM—Abstract.

Financial head—41.C.W.Provincial.

Budget head— Transferred.

Departmental head—Original Minor.

Main head— Police.

Sub-head.

Project of the work forms part—

Section—

Name of work—Electric installation to Town Police station Mangalore.

Amount of estimate, Rs. 570/-

To be carried out by—Electricity Deptt.,

REFERENCES.

Ref:--No.R.C.2375/Genl/34 dated 29-4-35 and No.618/Genl/36 dated 28-2-36 from the District Superintendent of Police, South Kanara District Mangalore.

Ref:--No.R.C.2930/Genl/36 dated 14-1-37 from the Dist.Superintendent of Police South Kanara Dist.Mangalore

ELECTRICITY DEPARTMENT.

Received ..... 19 *Registered* 19

Subject.

Electric Installation - South Kanara District - Mangalore - Police Buildings.

ENCLOSURES.
No. .....
.....
Spare copies .....

No. 13940/36-A-5

Station Chepauk, Madras, *Dated the* 23rd April 1937

From (Name) H.G. HOWARD ESQ.,

(Designation) Chief Engineer for Electricity

To The Secretary to the Government of Madras,

PUBLIC WORKS Department.

Sir,

Ref:-Your Memorandum No.1327 C-37-1 dated 1-4-37.

The Electrical Engineer (General) reports that estimates for the District Forest Officers' (North and South) Bungalows and for the Inspection Bungalow at -- Mangalore have been prepared and sent to the respective heads of departments.

2. As a number of Government buildings at Mangalore have already been electrified, the electrification of the Police Buildings at Mangalore, may be

considered

considered independently.

for Chief Engineer (Electricity)

DMD/G.

11/17

Pwd

A. Sh. 2/4.

9/2/4

U/

OM 1327-C-37-1 dt 1-4-37...

Electric Installation South Kanara St. Mangalore. - Police Buildings.

The I.G. of Police has submitted proposals for the electrification of the Police buildings at Mangalore, South Kanara St. The C.E. for Electricity is requested to report whether there are any proposals for the electrification of other Govt Buildings at Mangalore & if so in what stage they are at present & whether they should not be clubbed with the above proposals & taken up for execution at the same time with ref to Govt No. PW 2127-W dt 28-9-35.

Despatched 31/1/37 Work portion

To

The C.E. for Electricity ✓

Copy to I.G. of Police ✓

SRN 31.3.37

KL 1/4

SM 1.4.

C.F. 16.

DRAFT FOR APPROVAL.

	Date.	Initials.
When received for fair copying		
When copied	4/3/36	
When examined		
When signed		
When despatched.		

SUBJECT :— Electric Installation - South Kanara - Mangalore - Police dept buildings - Expenditure Rs 2155/- Approved.

READ AGAIN ; dated 19.

" " " 19.

READ *ALSO* :—

No. From the I.G. of Police, No. Re 1049 HW3/36 dated 5-3-1937. Cf

" " " " " 19.

" " " " " 19.

Order / ~~Resolution~~ Ms. ~~Rout.~~ No. 1105, dated 5 — 6 — 1937.

Govt. approve an expenditure of Rs 2155/- (Rupees Two thousand one hundred & fifty five only) on the provision of electric installation in the following buildings at Mangalore - at the cost shown against each.

		Rs
P 34	(1) D.S. Police office	880
	(2) Reserve school, Armoury,	
P 54	& Reserve Inspector's office	425
P 74	(3) Hackney Carriage office	60
P 94	(4) Town Police Station	570
P 114	(5) Taluk Police Station	220
		2155

Carried out from the provision in the current year under "50 a Civil works — original works — Buildings Police & Minor works."

89
14537

KK
15/5

15/6

To

The CE (E) with plans & sketches

CE/BTR ✓ ✓

Police thro Home Sect

Secretariat
Mar
3/6/37

GM
16/5